



**County Engineer  
Environmental Engineer**  
233 W. Sixth Street  
Marysville, Ohio 43040  
P 937. 645. 3021  
F 937. 645. 3161

[www.unioncountyohio.gov/engineer](http://www.unioncountyohio.gov/engineer)

**Building Department**  
233 W. Sixth Street  
Marysville, Ohio 43040  
P 937. 645. 3018

**Marysville Operations Facility**  
16400 County Home Road  
Marysville, Ohio 43040  
P 937. 645. 3017  
F 937. 645. 3111

**Richwood Outpost**  
190 Beatty Avenue  
Richwood, Ohio 43344

*Public Service with integrity*

## ADDENDUM #1

FROM: Union County Engineers Office  
Josh Holtschulte

DATE: February 28, 2025

RE: **Supplying, Delivering and Installing Precast Concrete Box Beams And/Or Supplying and Delivering Precast Concrete Box Culverts**

PAGES: 1

---

This addendum supplements and amends the original Drawings and Specification issued and shall be taken into account in preparing proposals, and shall become a part of the Contract Documents.

1. The following are clarifications in response to questions we have received.
  - a. *Question: Do the box culverts have wingwalls/headwalls? Do these need to be installed as well?*  
**Answer: The box culverts do not include wingwalls or headwalls.**
  - b. *Question: Are we placing type 2 or 3 waterproofing on the box culverts?* **Answer: No, Type 2 or Type 3 waterproofing materials are not required for the box culverts. However, the successful bidder shall supply the appropriate quantity of a preformed butyl joint material (such as Conseal).**
  - c. *Question: Is the Waldo Road location 2 spans next to each other, or at different locations?*  
**Answer: The two box culverts on Waldo Road are next to each other at the same stream crossing location.**
2. Clarification on the installation of the box culverts: The successful bidder will be responsible for supplying the proper crane, crane operator and the necessary manpower, tools and equipment to set the box culverts at the Waldo Road site only. The successful bidder will not be responsible for the crane or setting the box culvert at the McKittrick Road site. The successful bidder will be responsible for supplying and delivering the box culverts and other materials listed for both sites. Union County will be responsible for the site preparation and backfilling at both sites.

**Please note and sign the bottom portion of 5.2 of the bid packet proposal acknowledging that this Addendum was received.**